

Log Series Standard Specifications

Floors	 2x10 Floor Joists @ 16" O.C. w/ Double Perimeter Band (12" O.C. on 31'-6" Wide Models) 3/4" T&G OSB Floor Decking Glued and Nailed Vinyl Floor Covering w/ 1/4" Luan (Per Plan) 25 oz. FHA Approved Carpet w/ 8 lb. Rebound Pad (Per Plan)
Walls	 2x6 Exterior Walls @ 16" O.C. w/ 7/16" OSB Sheathing 6" Mating Walls @ 16" O.C. w/ 7/16" OSB Sheathing 2x4 Interior Walls @ 16" O.C. Solid Headers w/ OSB Reinforcement 1/2" Drywall Throughout, Glued and Screwed 8'-0" Wall Height
Roof	 7/12 Pitch, Non-Storage Rafter Roof System @ 16" O.C. 16" Gable End Overhangs 16" Eave Overhangs, Fixed w/ Soffit and Fascia Installed when Possible 7/16" OSB Roof Sheathing Ice Shield Installed on Eave Overhangs Minimum 15# Tamko 36" Felt Paper Shingle Underlayment Vented Vinyl Soffit, Ribbed Aluminum Fascia, and Aluminum Drip Edge 30 Year Tamko Architectural Shingles Shingle Over Ridge Vent (Shipped Loose)
Insulation	 R-21 Fiberglass Exterior Wall Insulation w/ Vapor Barrier R-38 Fiberglass Ceiling Insulation w/ Vapor Barrier Exterior House Wrap
Exterior	 "D" Log Siding with "Butt and Pass" Corners Smooth Fiberglass Front Door w/ Sunburst, Composite Jambs, and Vinyl Brickmould (Per Plan) Smooth Fiberglass Rear Door w/ Half Glass, Composite Jambs, and Vinyl Brickmould (Per Plan) 6'-0" Vinyl Sliding Glass Door (Per Plan) Satin Nickel Schlage Lever Locks – Exterior Door Hardware and Dead Bolt – Keyed Alike MW Beige Low "E" Vinyl Double Hung Brickmould Windows w/ Screens and Argon Gas One Exterior Light Supplied for Each Door
Interior	 Knotty Pine T&G wall finish on side and end walls (white walls on other interior walls) Smooth Ceilings w/ White Primer Paint Solid Knotty Pine Interior Doors Satin Nickel Lever Style Hardware Privacy Hardware on Bathrooms and Master Bedroom Craftsman Oak Trim package Matching Windows Sills 16" Deep Linen and Pantry Shelving (4 Rows) Shirt and Skirt Shelving for Walk in Closets

Cabinetry	 Hickory Raised Panel Arch Kitchen Cabinets 2-1/2" Crown Molding and Under Cabinet Trim Dove Tail Drawers, 3/4" Shelves w/ 1 Pull-Out Tray 75 lb. Full Extension Drawer Glides w/ Soft-Action Close Mechanism on Base Cabinet Drawers Elevated Corner Wall Cabinet, Crown and Under Cabinet Trim High Pressure, Square Edge Laminate Top and Backsplash (Kitchen) Hickory Raised Panel Arch Bath Cabinets One-Piece Cultured Marble Vanity Top (Baths) Medicine Cabinet w/ Decorative Lighting
Plumbing and Heating	 Electric Baseboard Heat w/ Individual Wall Mounted Thermostats 50 Gallon Electric Water Heater Tuff-Pex Fresh Water Lines Stubbed (Code Dictates) PVC Drain, Waste, and Vents (Stubbed) Shut-Off Valves on All Fixtures Delta Leland Chrome Dual Handle Faucets in Baths 60" One Piece Fiberglass Tub/Shower w/ Anti-Scald Valves Elongated Water Closets, Water Saver 8" Deep, Double Bowl S/S Sink and Gooseneck Faucet w/ Pull-Down Spray in Kitchen Ice Maker Hook-Up (Recessed Box for On-Site Appliance)
Electrical	 200 AMP Main Service Panel w/ 40 Breaker Spaces Smoke Detectors and Carbon Monoxide Detectors (Per Code) Fan/Light Combination in All Baths 30" Kitchen Range Hood; Vented to Exterior Bedrooms Have One Switched Receptacle Brushed Nickel Ceiling Lights in Hall, Laundry, Kitchen, Dining Room, Foyer, and Walk In Closets Fluorescent Lights in all Closets Over 4' w/ Separate Switch Recessed Can Light Over Kitchen Sink w/ Separate Switch Two Pendant Lights Above Islands and Peninsulas (Per Plan) Wireless Door Chimes (1 in Front and 1 in Rear) (2) RG-6 TV and (2) Cat-5 Phone Jacks Wired for Electric Range (Per Plan)
Warranty	★ All Homes Come with a 10 Year Structural Warranty
Additional Specs For: Raised Ranch	 ★ Recessed Entry (Per Standard Floor Plan) ★ 4-Way Switch and 3'-0" Heating Unit for Foyer Area ★ Landing w/ Floor Vinyl and Stairs Up to Living Area w/ Carpet to Match Living Room (All Shipped Loose)
Саре	 Rafter Roof w/ 12/12 Pitch @ 16" O.C. and 5/8" OSB Floor Decking 8" Mating Walls @ 16" O.C. w/ 7/16" OSB Sheathing (2) Gable End Windows w/ Style and Type to Match First Floor 30" Prehung Interior Door with 24' of Interior Walls Plumbing and Electric Stubbed up for Future on-site Bath and Living Area
Two Story	 8" Mating Walls @ 16" O.C. w/ 7/16" OSB Sheathing Insulation Installed Around Perimeter Between Floor and Ceiling Plumbing Supply Lines Run on Second Floor to Drop Area All Siding for Second Story Shipped Loose
.	

★ Products may change at any time, with or without notice, depending on availability from the manufacturer and/or vendor or lcon Legacy Custom Modular Homes' decision to switch to a different product.

* Revised 7/12/2010